

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02126-00-00
Spot: W2NESE Sec/Twnshp/Rge: 7-11S-17W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: STEIN Well #: 6
County: ELLIS Total Vertical Depth: 3408 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	1115		
COND	15	42		
PROD	7	3401		

110.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2009 1:30 PM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: RANDY WEIGEL Company: T-N-T ENGINEERING, INC. Phone: (785) 737-3736

Proposed Plugging Method: Ordered 650 sxs 60/40 pozmix - 4% gel - 19 sxs gel spacer - 600# hulls.
Perf Tech perfed at 1750' - 1090' - 600' - 175'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2009 9:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

06/19/2009 - Fischer Well Service RIH with tubing to 3310'.
Allied rigged to tubing and pumped 19 sxs gel - followed with 100 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.
Pulled tubing to 1760'. Allied rigged to tubing and pumped 200 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.
Pulled tubing to 900'. Allied rigged to tubing and pumped 100 sxs cement with 100# hulls mixed in.
Pulled tubing to 550' - pumped 100 sxs cement with 100# hulls - no circulation.
Will let set until Monday 06/22/2009.
06/22/2009 - Fischer Well Service RIH and tagged cement at 515'.
Allied rigged to tubing and pumped 60 sxs cement to circulate to surface.
Pulled tubing. Rigged to 7" casing and pumped 5 sxs cement to top off 7" casing.
Rigged to 10" casing and pumped 60 sxs.
Max. P.S.I. 200#. S.I.P. 150#.
15" full to surface.

Perfs:

KANSAS CORPORATION COMMISSION
JUN 23 2009
RECEIVED

INVOICED
DATE 8-20-09
INV. NO. 2010060124

Remarks: ALLIED CEMENTING COMPANY-TICKET #37541.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

PKS

7-11-17W
W2 NE SE

DICKEY OIL CO

#6 STEIN

Contr.

ELLIS County

E 1851 Comm 3-19-41 Comp 4-16-41 IP

3000 BOPD
ECHO

Tops	Depth	Datum	Casing
ANH	1090		15" 42
			10" 1115
			7" 3401
CONG	3354		A/1000
SIMP	3384		
ARB	3401		
TD	3408		

--	--	--	--

1700 salt