

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00357-00-00
Spot: NENESW Sec/Twnshp/Rge: 31-17S-12W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: W.M. EVELEIGH Well #: 1
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| CIBP | | 3068 | | |
| SURF | 8.625 | 706 | 0 | 350 SX |
| PROD | 5.5 | 3430 | 0 | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2009 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing to be pulled. Started to pull casing - found collars were welded - decided not to pull casing. Set casing down.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2009 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing - started to pull casing - collars were welded - decided not to pull - set casing back down.
Tied to casing - pumped 150 sxs cement with 300# hulls.
Ran perfing tool to 539' - tied to casing - pumped 230 sxs cement with 200# hulls - cement did not circulate. Shut down.
06/08/2009 - Tagged cement at 190' - ran 1" tubing in backside to 130' - pumped 60 sxs cement - circulated to surface.
Pulled 1" - ran down casing to 130' - pumped 20 sxs cement - cement circulated to surface.
Pulled 1" - hole stayed full.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3152 | 3156 | | LKC |
| 3132 | 3134 | | |
| 3090 | 3095 | | |
| 3083 | 3086 | | |
| 2918 | 2924 | | TOPEKA |

INVOICED
DATE 8-17-09
INV. NO. 2010060108

RECEIVED
JUN 18 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM
PRT

Form CP-2/3

JUN 12 2009