

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
9-26-66  
SEP 26 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Miller of L. J. Dreiling & Sons Drl. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name: Baldwin "B" Well No. 1

Location: C N/2 N/2 SE Sec. 9 Twp. 10 Rge. 19 (E)(W) X

County Rooks Total Depth 3755' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace 25 sc cement thru drill pipe. Heavy mud to 160' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 8 sc cement to base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

Leo J. Roberts  
Conservation Division Agent