

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM

NOV 21 2005

WELL HISTORY - DESCRIPTION OF WELL & LEASE
CONFIDENTIAL

KCC WICHITA

Operator: License # 5254
Name: MIDCO Exploration, Inc.
Address: 414 Plaza Drive, Suite 204
City/State/Zip: Westmont, IL 60559
Purchaser: ONEOK
Operator Contact Person: Earl J. Joyce, Jr.
Phone: (630) 655-2198
Contractor: Name: Duke Drilling Co., Inc.
License: 5929
Wellsite Geologist: N/A

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

9/28/05 10/03/05 10/15/05
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 095-21985-0000
County: Kingman
NW SE NW Sec. 35 Twp. 28 S. R. 8 East West
1485 feet from S / (N) (circle one) Line of Section
2145 feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE (NW) SW
Lease Name: Ramsey Well #: 4

Field Name: Garlich SW
Producing Formation: Mississippi
Elevation: Ground: 1637' Kelly Bushing: 1645'
Total Depth: 4250' Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 253 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan Att I WHM 43-07
(Data must be collected from the Reserve Pit)
Chloride content 17,000 ppm Fluid volume 700 bbls
Dewatering method used vacuum free fluids
Location of fluid disposal if hauled offsite:
Operator Name: Messenger Petroleum, Inc.
Lease Name: Nicholas SW License No.: 4706
Quarter _____ Sec. 20 Twp. 3 S. R. 8 East West
County: Kingman Docket No.: D-25,073

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: Vice-President Date: 11/17/2005

Subscribed and sworn to before me this 17th day of November,
2005.

Notary Public: Nancy L. Macyunas
"OFFICIAL SEAL"
Nancy L. Macyunas
Notary Public, State of Illinois
My Commission Exp. 06/24/2006

KCC Office Use ONLY
Yes Letter of Confidentiality Received
If Denied, Yes Date: _____
____ Wireline Log Received
____ Geologist Report Received
____ UIC Distribution

CONFIDENTIAL

Slide Two

ORIGINAL

Operator Name: MIDCO Exploration, Inc. Lease Name: Ramsey Well #: 4

Sec. 35 Twp. 28 S. R. 8 East West County: Kingman

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No

List All E. Logs Run:

- Dual Induction
Dual Compensated Porosity
Microlog
BHC Sonic
Cement Bond

Table with columns: Log, Formation (Top), Depth and Datum, Sample. Includes entries for Heebner, Toronto, Lansing, Hertha, and Mississippi with depths and datums.

CASING RECORD table with columns: Purpose of String, Size Hole Drilled, Size Casing Set, Weight Lbs./ Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Includes Surface and Production rows.

ADDITIONAL CEMENTING / SQUEEZE RECORD table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives.

PERFORATION RECORD table with columns: Shots Per Foot, Bridge Plugs Set/Type, Acid, Fracture, Shot, Cement Squeeze Record, Depth. Includes a row for 2 shots at 4090-4100'.

TUBING RECORD table with columns: Size, Set At, Packer At, Liner Run. Includes entry for 2 3/8" size, set at 4070.

Table with Date of First Resumerd Production (10/26/2005) and Producing Method (Flowing).

Table with Estimated Production Per 24 Hours: Oil Bbls. (250), Gas Mcf (80), Water Bbls., Gas-Oil Ratio, Gravity.

Disposition of Gas, METHOD OF COMPLETION, Production Interval. Includes checkboxes for Vented, Sold, Used on Lease, Open Hole, Perf., Dually Comp., Commingled, Other.

RECEIVED
NOV 21 2005
KCC WICHITA

ALLIED CEMENTING CO., INC. 20954

MIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
MEDICINE LODGE

DATE <u>9-28-05</u>	SEC. <u>35</u>	TWP. <u>28S</u>	RANGE <u>08W</u>	CALLED OUT <u>12:30pm</u>	ON LOCATION <u>1:00 pm</u>	JOB START <u>3:45pm</u>	JOB FINISH <u>5:00pm</u>
LEASE <u>RAVSEY</u>		WELL # <u>4</u>		LOCATION <u>SPRING, BALLPARK RD., 9 N TO STOP</u>		COUNTY <u>KLINGMAN</u>	STATE <u>KS</u>
OLD OR <u>(NEW)</u> (Circle one)				<u>SIGN, THEN 1 3/4 N, EAST INTO</u>			

CONTRACTOR DUKE #2

TYPE OF JOB SURFACE CASING

HOLE SIZE 12"4" T.D. 253'

CASING SIZE 8 3/8" DEPTH 253'

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2" DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 250 MINIMUM 50

MEAS. LINE _____ SHOE JOINT 15'

CEMENT LEFT IN CSG. 15'

PERFS. _____

DISPLACEMENT 15 bbl. FRESH WATER

OWNER MIDCO EXPLORATION

CEMENT

AMOUNT ORDERED 250 sk 60:40:2+3% cc.

COMMON	<u>150</u>	@	<u>8.70</u>	<u>1305.00</u>
POZMIX	<u>100</u>	@	<u>4.70</u>	<u>470.00</u>
GEL	<u>4</u>	@	<u>14.00</u>	<u>56.00</u>
CHLORIDE	<u>8</u>	@	<u>38.00</u>	<u>304.00</u>
ASC		@		

EQUIPMENT

PUMP TRUCK CEMENTER BILL M.

397 HELPER CHRIS A.

BULK TRUCK

389 DRIVER STEVE K.

BULK TRUCK

_____ DRIVER _____

RECEIVED

NOV 21 2005

KCC WICHITA

HANDLING	<u>262</u>	@	<u>1.60</u>	<u>419.20</u>
MILEAGE	<u>40 x 262 x .06</u>			<u>628.80</u>
TOTAL				<u>3183.00</u>

REMARKS:

PIPE ON BOTTOM, BREAK CIRCULATION,
PUMP 5 bbl. FRESH WATER (PRE-FLUSH), PUMP 250
sk 60:40:2+3% cc, STOP PUMPS, RELEASE
PLUG, START DISPLACEMENT, DISPLACE
WITH 15 bbl. FRESH WATER, STOP PUMPS,
SHUT-IN, CIRCULATED CEMENT, RIG DOWN.

SERVICE

DEPTH OF JOB 253'

PUMP TRUCK CHARGE _____ 670.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 40 @ 5.00 200.00

MANIFOLD HEAD RENT @ 75.00 75.00

_____ @ _____

_____ @ _____

TOTAL 945.00

CHARGE TO: MIDCO EXPLORATION

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>8 3/8" WOODEN PLUG</u>	<u>1</u>	@	<u>55.00</u>	<u>55.00</u>
_____		@		
_____		@		
_____		@		
_____		@		
TOTAL				<u>55.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING

SIGNATURE David A Mayfield

TAX _____

TOTAL CHARGE ~~945.00~~

DISCOUNT ~~220.00~~ IF PAID IN 30 DAYS

DAVID MAYFIELD

PRINTED NAME

ALLIED CEMENTING CO., INC. 20960

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
MEDICINE LODGE

DATE <u>10-4-05</u>	SEC. <u>35</u>	TWP. <u>28s</u>	RANGE <u>08W</u>	CALLED OUT <u>4:30 am</u>	ON LOCATION <u>7:00 am</u>	JOB START <u>9:30 am</u>	JOB FINISH <u>11:20 am</u>
LEASE <u>KAMSEY</u>		WELL # <u>4</u>	LOCATION <u>SPIVEY HALL PARK RD, 9 N TO STOP</u>		COUNTY <u>KINGMAN</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)			SIGN, THEN <u>1 3/4 N, E INTO</u>				

CONTRACTOR DUKE #2

TYPE OF JOB PRODUCTION CASING

HOLE SIZE <u>7 7/8"</u>	T.D. <u>4,250'</u>
CASING SIZE <u>4 1/2"</u>	DEPTH <u>4,249'</u>
TUBING SIZE	DEPTH
DRILL PIPE <u>4 1/2"</u>	DEPTH
TOOL	DEPTH
PRES. MAX <u>1,100</u>	MINIMUM <u>100</u>
MEAS. LINE	SHOE JOINT <u>36.46</u>
CEMENT LEFT IN CSG. <u>36.46'</u>	

OWNER MIDCO EXPLORATION

CEMENT

AMOUNT ORDERED 25 x 60:40:4 (CAT & MOUSE)
190 x ASC + 5" KOL-SEAL/SACK + 7% GAS BLOCK,
500 GAL. ASF, 500 GAL. MUD CLEAN C, 7 GAL. CLAPRO

PERFS.

DISPLACEMENT 66 3/4 bbl. 2% KCL WATER

COMMON <u>15</u> A	@ <u>8.70</u>	<u>130.50</u>
POZMIX <u>10</u>	@ <u>4.70</u>	<u>47.00</u>
GEL <u>1</u>	@ <u>14.00</u>	<u>14.00</u>
CHLORIDE	@	
ASC <u>190</u>	@ <u>10.75</u>	<u>2042.50</u>
<u>Kol Seal 950</u>	@ <u>6.00</u>	<u>570.00</u>
<u>Gas Block 125</u>	@ <u>7.40</u>	<u>925.00</u>
<u>ASF 500 gal</u>	@ <u>1.00</u>	<u>500.00</u>
<u>Mud Clean C 500 gal</u>	@ <u>1.25</u>	<u>625.00</u>
<u>Clap Pro 7 gal</u>	@ <u>22.90</u>	<u>160.30</u>
	@	
	@	
	@	
HANDLING <u>272</u>	@ <u>1.60</u>	<u>435.20</u>
MILEAGE <u>40 x 272 x .06</u>		<u>652.80</u>
TOTAL		<u>6102.30</u>

EQUIPMENT

PUMP TRUCK # <u>368</u>	CEMENTER <u>BILL M.</u>
	HELPER <u>DWAYNE W.</u>
BULK TRUCK # <u>381</u>	DRIVER <u>JERRY C.</u>
BULK TRUCK #	DRIVER

REMARKS:

PIPE ON BOTTOM, BREAK CIRCULATION, PUMP
PIG-FRUSH, STOP PUMP, PLUG RAT & MOUSE HOLES
WITH 25 x 60:40:4, STOP PUMPS, PUMP 190 x
ASC + 5" KOL-SEAL/SACK + 7% GAS BLOCK, STOP
PUMPS, WASH PUMP & LINES, RELEASE PIG,
START DISPLACEMENT, SEC LIFT, SLOW RATES
BUMP PIG, FLOAT HEAD, DISPLACED WITH
66 3/4 bbl. 2% KCL WATER.

SERVICE

DEPTH OF JOB <u>4,249'</u>	
PUMP TRUCK CHARGE	<u>1370.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>40</u>	@ <u>5.00</u> <u>200.00</u>
MANIFOLD HEAD RENT	@ <u>75.00</u> <u>75.00</u>
	@
	@

RECEIVED

NOV 21 2005

KCC WICHITA

TOTAL 1645.00

CHARGE TO: MIDCO EXPLORATION

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>4 1/2" RUNNER PLUG</u>	<u>1</u> @ <u>48.00</u>	<u>48.00</u>
<u>4 1/2" GUIDE SHOE</u>	<u>1</u> @ <u>125.00</u>	<u>125.00</u>
<u>4 1/2" AFU INSERT</u>	<u>1</u> @ <u>210.00</u>	<u>210.00</u>
<u>4 1/2" CENTRALIZERS</u>	<u>5</u> @ <u>45.00</u>	<u>225.00</u>
<u>4 1/2" TURBOIZERS</u>	<u>5</u> @ <u>55.00</u>	<u>275.00</u>

TOTAL 883.00

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on ANY APPLICABLE TAX

WILL BE CHARGED UPON INVOICING

TAX _____

TOTAL CHARGE ~~1645.00~~

DISCOUNT ~~1645.00~~ IF PAID IN 30 DAYS

SIGNATURE David A. Mayfield

DAVID MAYFIELD

PRINTED NAME