

Operator Name: R & B Oil & Gas, Inc. Lease Name: ALBRIGHT Well #: 2
 Sec. 17 Twp. 31 S. R. 8 East West County: Harper

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: <p style="text-align: center;">Dual Induction Dual Compensated Porosity</p>	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum <p style="text-align: center;">Miss 4393 (-2772)</p>
---	--

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	8-5/8"	23#	284'	PozmixA	200	4 Gell & 7% salt
Production	7-7/8"	5 1/2"	14#	4861'	Class A	175	10% Salt & 5# Kalseal

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4394 - 4410	Acid 1100 gal 7 1/2% HCL	
		Frac 120 sx 100 mesh	
		210 sx 16/30 Sand	
		85 sx CRC 16/30 Sand	

TUBING RECORD		Size <u>2-7/8"</u>	Set At <u>4519'</u>	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. <u>10-10-07</u>		Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil <u>8</u> Bbls.	Gas <u>75</u> Mcf	Water <u>150</u> Bbls.	Gas-Oil Ratio <u>9.375 - 1</u>	Gravity <u>32°</u>

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 20 2007

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC. 31173

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Med Lodge

DATE <u>8-24-07</u>	SEC. <u>17</u>	TWP. <u>31S</u>	RANGE <u>06W</u>	CALLED OUT <u>6:15pm</u>	ON LOCATION <u>8:30pm</u>	JOB START <u>11:30pm</u>	JOB FINISH <u>12:00am</u>
LEAS. <u>Albright</u>	WELL # <u>#2</u>	LOCATION <u>Attica KS 1 1/2 rd Harper</u>		COUNTY <u>Harper</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one) <u>NEW</u>		<u>130</u>	<u>1/2 E</u>	<u>N into</u>			

CONTRACTOR H. Gault #1 OWNER R+B Oil & Gas

TYPE OF JOB Surface

HOLE SIZE 12 1/4 T.D. 285 CEMENT AMOUNT ORDERED 200 2 1/2 60/40

CASING SIZE 8 5/8 DEPTH 285 2+3

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 200 MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 15 ft

PERFS.

DISPLACEMENT 17 bbls Water

COMMON	<u>120 A</u>	@	<u>11.10</u>	<u>1332.00</u>
POZMIX	<u>80</u>	@	<u>6.20</u>	<u>496.00</u>
GEL	<u>4</u>	@	<u>16.65</u>	<u>66.60</u>
CHLORIDE	<u>7</u>	@	<u>46.60</u>	<u>326.20</u>
ASC		@		
HANDLING	<u>211</u>	@	<u>1.90</u>	<u>400.90</u>
MILEAGE	<u>30 x 211 x .09</u>			<u>569.70</u>
TOTAL				<u>3191.40</u>

EQUIPMENT

PUMP TRUCK CEMENTER R+B

372 HELPER Dain

BULK TRUCK DRIVER Heath

363 DRIVER

BULK TRUCK DRIVER

REMARKS:

*Pipe on bottom + Circulate
Pump fresh mix 200 2 1/2
60/40 2+3 shut down
Pump. Release plug + start
displacement. Stop rate
Pump 17 bbls + Shut in +
Cement did circulate.*

SERVICE

DEPTH OF JOB	<u>285</u>		
PUMP TRUCK CHARGE			<u>815.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30</u>	@	<u>6.00</u>
MANIFOLD		@	
<u>Head rental</u>		@	<u>100.00</u>
TOTAL <u>1095.00</u>			

CHARGE TO: R+B Oil & Gas

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>8 5/8</u>			
<u>1-wooden plug</u>	@	<u>60.00</u>	<u>60.00</u>
	@		
	@		
	@		

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TOTAL 60.00

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Scott C Adelman
I have you &

PRINTED NAME _____

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 20 2007
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

31303

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medford KS

DATE <u>9-3-07</u>	SEC. <u>17</u>	TWP. <u>31S</u>	RANGE <u>08W</u>	CALLED OUT <u>4:30pm</u>	ON LOCATION <u>9:00pm</u>	JOB START <u>12:25am</u>	JOB FINISH <u>1:30am</u>
LEASER <u>Albright</u>	WELL # <u>2</u>	LOCATION <u>Attica KS N to Rd 130</u>		COUNTY <u>Hays</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)			<u>1/2 E N into</u>				

CONTRACTOR Hagalt #1
 TYPE OF JOB Pipe cement
 HOLE SIZE 7 7/8 T.D. 4863
 CASING SIZE 5 1/2 DEPTH 4862
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 1400 MINIMUM 200
 MEAS. LINE _____ SHOE JOINT 41
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT 118 bbls 28 KCL

OWNER R+B Oil + Gas
 CEMENT
 AMOUNT ORDERED 400 lb 60/110 4 + 485 lb
175 lb H 102 root + 5# seal
500 gal ASF + 13 gal Claypro

EQUIPMENT
 PUMP TRUCK CEMENTER Mark B
 # 370 HELPER Darin
 BULK TRUCK DRIVER Heath
 # 356
 BULK TRUCK DRIVER _____
 # _____

COMMON	<u>24</u>	<u>A</u>	@	<u>11.10</u>	<u>266.40</u>
POZMIX	<u>16</u>		@	<u>6.20</u>	<u>99.20</u>
GEL	<u>2</u>		@	<u>16.65</u>	<u>33.30</u>
CHLORIDE			@		
ASC			@		
	<u>175</u>	<u>H</u>	@	<u>13.40</u>	<u>2345.00</u>
	<u>SALT</u>	<u>19</u>	@	<u>9.60</u>	<u>182.40</u>
	<u>ASF</u>	<u>500 gal.</u>	@	<u>1.00</u>	<u>500.00</u>
	<u>Claypro</u>	<u>13 gal.</u>	@	<u>25.00</u>	<u>325.00</u>
	<u>Sodium Metasilicate</u>	<u>14#</u>	@	<u>1.95</u>	<u>27.30</u>
	<u>Kol Seal</u>	<u>875#</u>	@	<u>.70</u>	<u>612.50</u>
			@		
			@		
HANDLING	<u>254</u>		@	<u>1.90</u>	<u>482.60</u>
MILEAGE	<u>30 x 254</u>		X	<u>.09</u>	<u>685.80</u>
					TOTAL <u>5559.50</u>

REMARKS:

Pipe on bottom + Circulate pump 20 bbls
 28 KCL, 3 bbls fresh, 500 gal ASF, 3 fresh
 plug rat hole, mix 25% scavenger
 + 175# tail shut down pump,
 Wash pump + line + release plug
 start displacement, lift pressure
 at 84 bbls, slow rate to 3 bpm
 at 107 bbls, bump plug at 118 bbls
 20 pre-blot did not bleed

CHARGE TO: R+B Oil + Gas
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<u>4862</u>		
PUMP TRUCK CHARGE			<u>1750.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30</u>	@	<u>6.00 180.00</u>
MANIFOLD		@	
		@	<u>100.00 100.00</u>
RECEIVED		@	
KANSAS CORPORATION COMMISSION			
DEC 20 2007			TOTAL <u>2030.00</u>

CONSERVATION DIVISION
 WICHITA SUG & FLOAT EQUIPMENT

<u>5 1/2</u>			
<u>1- Guide Shoe</u>	@	<u>170.00</u>	<u>170.00</u>
<u>1- AFU insert</u>	@	<u>260.00</u>	<u>260.00</u>
<u>8- Turbolynne</u>	@	<u>70.00</u>	<u>560.00</u>
<u>10 Scratchers</u>	@	<u>65.00</u>	<u>650.00</u>
<u>1- Rubber plug</u>	@	<u>65.00</u>	<u>65.00</u>
ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING			
			TOTAL <u>1705.00</u>

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment
 and furnish cementer and helper to assist owner or
 contractor to do work as is listed. The above work was
 done to satisfaction and supervision of owner agent or
 contractor. I have read & understand the "TERMS AND
 CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE [scribble]
 DISCOUNT [scribble] IF PAID IN 30 DAYS

SIGNATURE Tom Pierce

X TIM PIERCE
 PRINTED NAME