

15-051-19237-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
10-25-1963  
OCT 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Whitestone Pet Co  
Complete Address: 900 Vaughn Bldg Dallas, Texas  
Lease Name Chrisler Well No. 1  
Location NW NW NE Sec. 9 Twp. 12 Rge. (E) (W) 16  
County Ellis Total Depth 3450  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: L. J. Dreiling & Sons & Halliburton Co  
Address: Victoria, Kans License No.       
Operation Completed: Hour 10PM Day 22 Month 10 Year 63

The Above well was plugged as follows:

8 5/8" 200' circulated with cement.  
Circulated hole with heavy mud, set wiper plug at 400', displaced 20 sax  
cement through drill pipe, heavy mud to 180', set plug and displaced 20  
sax cement through drill pipe, heavy mud to 35', set plug, 1/2 sack hulls  
and filled with cement to bottom cellar.  
Cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/28/63  
INV. NO. 7966-W

Signed: Edson Peery  
Well Plugging Supervisor