

15-051-20598-00-00

KANSAS

Form CP-3
Rev. 6-4-68

61

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-24-1970
MAR 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company

Complete Address Victoria, Kansas

Lease Name Dickinson S Well No. 5

Location SE SE SW Sec. 10 Twp. 12 Rge. (E) (W) 16

County Ellis Total Depth 3370

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 6P Day 19 Month 3 Year 1970

The above well was plugged as follows:

RTD 3370' 8 5/8 csg set at 167' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 480' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 160' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-24-70

INV. NO. 1629-42

Signed: Leo J. Massey
Well Plugging Supervisor