

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01952-00-00
Spot: NESWSW Sec/Twnshp/Rge: 18-10S-19W
990 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: SCOGGINS Well Number: 3
County: ROOKS Total Vertical Depth: 3773 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3768 200 SX CMT
Surface Casing Size: 8.625 feet: 1627 650 SX CMT

\$122⁶²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2003 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: PAUL BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 18 sxs gel - 500# hulls.
Perfs at 900' and 1700'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/12/2003 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 3495' - spotted 18 sxs gel followed with 40 sxs cement with 300# hulls mixed in cement.
Pulled tubing to 1700' - circulated cement to surface with 140 sxs cement with 200# hulls mixed in cement.
POOH with tubing and squeezed 60 sxs cement to Max. P.S.I. 1000#. Shut in.
Pumped down 8 5/8" S.P. with 25 sxs cement.
S.I.P. 300#.

RECEIVED
10-30-03
OCT 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

10

INVOICED
DATE 10-20-03
INVOICE NO. 2004060694

OCT 23 2003

SKELLY OIL CO. #3 SCOGGINS ²² Arb 18-10-19W
NE SW SW

Contr. _____ HOOKS _____ County

E 2226 Comm. _____ Comp. 6-10-49 IP 2539 BOPD

Tops	Depth	Datum	Casing	
			8" 1627	DP 3773
HEEB	3421	-1195	5" 3768	2600' 01H/12 HRS ACID 500
LANS	3458	-1232		240 BO/12 HR. ACID 750
CONG	3701	-1475		PMP 173 BO & 6 BW/ 8 HRS
SIMP	3753	-1527		
ARB	3767	-1541		
T.D.	3773	-1547		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS