

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01946-00-00
Spot: CNWNWNW Sec/Twnshp/Rge: 18-10S-19W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: MARCOTTE Well Number: 6
County: ROOKS Total Vertical Depth: 3766 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size _____ feet: 8/22.40
Surface Casing: Size 8.625 feet: 163
Production: Size 5.5 feet: 3763
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2002 9:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 335 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/02/2002 11:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 163'. 5 1/2" casing at 3763'.
Squeezed at 1030' with 150 sxs cement.
Ran tubing to 2000' - spotted 100 sxs cement and 300# hulls.
Pulled tubing to 1076' - circulated with 60 sxs cement and 250# hulls.
Pulled all tubing and squeezed with 10 sxs cement to Max. P.S.I. 500#. S.I.P. 500#.
Tied to annulus and squeezed 75 sxs cement to Max. P.S.I. 250#. S.I.P. 100#.
Total of 245 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED
7-18-02
JUL 18 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. BLACKHAWK TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 7-18-02

WV. NO. 2003060.041

JUL 17 2002

BIRMINGHAM BARTLETT DRLG. CO. #6 MARCOTTE 18-10-19W 22
 NW NW NW

Contr. BIRMINGHAM BARTLETT DRILLING CO. BOOKS County

F. 2221 Comm. 7-1-50 Comp. 8-1-50 IP. 421 BOFD
 PHY POT

Tops	Depth	Datum	Casing
ANH	1616	+578	8" 163 1,240' OIH/2 HRS
HEFR	3122		5" 3763
LANS.	3162	-1238	
B/KC	3673		
CONG	3698	-1474	
SIMP	3736	-1512	
ARB	3761	-1537	
T.D.	3766		

BERLAND POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS