

4-20 15-163-01945-000 <sup>232</sup>

6 041167

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5245  
Operator: Okmar Oil Co  
Name & Address: Box 723  
Hays, Ks. 67601

API NUMBER 15-4-5  
SW NW NW SEC. 18, T 10 S, R 19 W/EX  
4290 feet from S section line  
4950 feet from E section line  
Lease Name Marcotte Well # 5  
County Rooks 122.88  
Well Total Depth 3781 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 1/2 feet 184' w/150 sks.

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_  
Address Hays, Ks.

Company to plug at: Hour: 10:00 AM Day: 20 Month: April Year: 19 90

Plugging proposal received from Bob Grant  
(company name) Okmar (phone) \_\_\_\_\_

were: 5 1/2" at 3777' w/150 sks cement. O.H. 3780. Sq at 1200' cement n.a. Perf  
1650'; and base dakota 950': perf base of s.p. 184'. Ordered 350 sks 65/35 poz 10%  
gel w/1/4# f.c. plus 4 sks hulls..

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 5:30PM Day: 20 Month: April Year: 19 90

ACTUAL PLUGGING REPORT R.I.H. w/tubing to 3676'; spt. 90 sks cement w/2 sks  
hulls: pull tubing to 2700'; spot 135 sks cement w/1 sk hulls. Cement circ to surf  
P.O.O.H. w/tubing: Hooked up to 5 1/2" casing and sq add 125 sks cement; Max 1000# S.I. 350#.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 5-9-90  
INV. NO. 28079

Signed Dennis L. Hamel  
(TECHNICIAN)