

9-28 15-163-01944-0000

4-041517

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 2-24-50

NW SW NW /4 SEC. 18, 10 S, 19 W
3960 feet from S section line
4950 feet from E section line

Operator license# 5363

Lease Marrotte well # 4

Operator: Berexco, Inc.

County Rooks

Address: Box 723
Hays, Kansas 67601

Well total depth 3799 feet ^{123.45}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 194 feet
w/150 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 28 Month: September Year: 93

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone: 913-628-6101

Were: 5 1/2" casing set @ 3799' w/200 sx. cement. Perf. @ 3544' -
3778'. Salt @ 3799' - Anhy. @ 1700' - Dakota @ 800'. 4 1/2" liner
1678'. Cemented to surface.
Ordered 300 sx. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 3:30P.M., Day: 28, Month: September, Year: 93

Actual plugging report: Perf. casing @ 1700' and 800'. R.I.H. with
tubing to 3550'. Spot 50 sx. cement with 200# hulls. Pull tubing to
2500'. Spot 50 sx. cement with 100# hulls. Pull to 1700'. Spot 50
sx. cement with 100# hulls. Pull to 800'. Spot 50+. Circulate to
surface. Squeeze at surface with 50 sx. Hooked-up to 8 5/8" S.P.
Squeeze 50 sx. cement with 100# hulls.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2222

INVOICED did not [] observe the plugging.

Dennis L. Hamel
Conservation Division
Wichita, Kansas

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
10-6-93
OCT 06 1993
CONSERVATION DIVISION
Wichita, Kansas

DATE 10-7-93
INV. NO. 38895

HO