

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01943-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 18-10S-19W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: MARCOTTE Well Number: 3  
County: ROOKS Total Vertical Depth: 4030 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Production Casing Size: 5.5 feet: 3767 200 SX CMT  
Surface Casing Size: 8.625 feet: 207 160 SX CMT

*130 98*

Well Type: SWD UIC Docket No: D23733.0 Date/Time to Plug: 07/14/2003 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls - 30 sxs sand.  
Emergency plug with rig over hole.  
Perfs 3596' - 3606'. Open hole 3760' - 4030'.  
Alt II done 1984.  
Perf 1695' cwc 350 sxs when converted to SWD.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/14/2003 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Berexco RIH with tubing to 3457' - spotted 30 sxs sand to 3730' - left set 1 1/2 hours.  
Allied tied onto backside - pumped 25 sxs 60/40 pozmix with Max. P.S.I. 200#. S.I.P. 50#.  
Pulled tubing to 3395' - pumped 50 sxs 60/40 pozmix with 300# hulls.  
Pulled tubing to 2156' - pumped 210 sxs 60/40 pozmix with 200# hulls - cement circulated.  
Pulled tubing and tied onto 5 1/2" casing with a swedge - pumped 30 sxs 60/40 pozmix with Max. P.S.I. 900#. S.I.P. 850#.

RECEIVED  
7-28-03  
JUL 28 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET#15706.

Plugged through: TBG

District: 04

*110*

Signed

(TECHNICIAN)

INVOICED

DATE 7-28-03

INV. NO. 2004060242

JUL 23 2003


BIRMINGHAM-BARTLETT DRILLING CO. # 3 MARCOTTE 13-10-19W  
 SV SW NW

Contr. BIRMINGHAM-BARTLETT DRILLING CO. ROOKS County

E 2231 RB Comm. Comp. 12-9-49 IP 761 80 PD  
 PHY POT

Tops	Depth	Datum
HEEB	3424	-1193
DODGE	3441	-1210
LANS	3462	-1231
CCNG	3701	-1470
SIMP	3753	-1522
ARB	3765	-1534
TD	3781	-1550

Casing  
 8" 207 DP 3766  
 SWB 15 B0/3 HRS  
 5" 3767 DD 3773  
 SWB 40 BF/7 HRS: 70% WTR  
 DD 3781: NS: PB 3748  
 PERF 47-S, 3596-3608  
 ACID 1000  
 SWB 20 BOPH/2 HRS



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS