

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01971-00-00
Spot: NWNESW Sec/Twnshp/Rge: 18-10S-19W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SCOGGINS 3795 Well Number: 12
County: ROOKS Total Vertical Depth: 3775 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3773 500 SX CMT
Surface Casing Size: 8.625 feet: 313 150 SX CMT

PT KCC
12269

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2003 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: PAUL BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 18 sxs gel - 500# hulls.
Perfs at 900' and 1700'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/09/2003 5:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Ran tubing to 3700' - spotted 18 sxs gel followed with 40 sxs cement with 300# hulls.
Pulled tubing to 1700' - spotted 120 sxs cement with 200# hulls to circulate at surface.
POOH with tubing and squeezed 30 sxs cement to Max. P.S.I. 700#. S.I.P. 500#.
8 5/8" S.P. - pressured up to 800# - no cement pumped.

RECEIVED
10-30-03
OCT 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

INVOICED

10-30-03
2004060694

Form CP-2/3

OCT 28 2003

SKELLY OIL CO

#12 SCOGGINS

18-10-19W 22

NW NE SW

Contr. WENTWORTH

ROOKS

County

E. 2237RB Comm.

Comp. 3-7-52

IP 358 BOPD (KC.)

PHY POT

Tops	Depth	Datum
HEEB	3130	-1193
LANS	3166	-1229
CONG	3709	-1172
ARB	3773	-1536
T.D.	3775	-1538

Casing

8" 313

5" 3773

PMP 48 B0 & 192 BW/12
 HRS: PB 3700: PERF 12S
 3654-7, ACID 1500: SWB
 50 B0/10 HRS: PB 3610:
 PERF 12S 3622-25: PMP
 222 B0/22 HRS.

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS