

4 050020

X 1-16

(u)

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-20,107-0001 21,699
SW NE NE, SEC. 18, T 10 S, R 19 W/EX
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6273

Lease Name Anderson Well # 11
County Rooks 130.88

Operator: Robert R. Price Operations, Inc
Name & Address: Box 470442
Tulsa, Ok. 74147

Well Total Depth 4027 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well XX D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B J Titaw License Number _____

Address Hays Ks

Company to plug at: Hour: 9:30 AM Day: 16 Month: Jan Year: 19 90

Plugging proposal received from Robert R. Price

(company name) Bottom plugged off by operator as follows: (phone) 918-492-1684

were: Ran packer to 2100' pumped 175 sks common cement down 5 1/2" casing w/1000 psi. Pulled packer to 650' pumped 400 sks 60/40 poz 6% gel down 5 1/2" casing w/1500 psi. Drilled cement

to 1010' pressured up leaked off. Pumped 250 sks 60/40 poz 6% gel down 5 1/2" casing leaked off. Pumped 300 sks down backside w/1000 psi held.

Reset packer again at 650' pumped 250 sks down 5 1/2" w/1500 psi. Drilled cement to 1143'.

Prepared to plug well.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 11:45 AM Day: 16 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT State witnessed plugging from 1143' to surface as follows:

Ran wireline to 1143'. Perforated at 930'. Pumped 115 sks 60/40 poz 6% gel down 5 1/2" casing with max psi at 350'. Shut in psi at 300'. Tied onto backside pumped 0 sks w/600 psi. Checked cement top on Jan 18, 1990. Cement 10' from surface.

RECEIVED
STATE CORPORATION COMMISSION
2-14-90
FEB 14 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby observe this plugging.

DATE 2-16-90

INV. NO. 27476

1-16

G.S.

Signed Marvin Miller
(TECHNICIAN)

Marvin Miller