

15-163-01955-0002 *new permit*

To: **6** 031289
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1949
RT SW NE SW SEC. 18, T 10 S, R 19 *W/E*
1650 ~~7290~~ feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6931
Operator: Bowman Oil Co.
Name & Address Box 17
Codell, Ks. 67630

Lease Name Scoggins Well # 6
County _____ Rooks 124.800
Well Total Depth 3840 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1635'

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement Co. License Number _____
Address Hays, Ks.

Company to plug at: Hour: PM Day: 18 Month: Oct Year: 19 89

Plugging proposal received from Don Bowman
(company name) Bowman Oil (phone) _____

were: 8 5/8" set at 1635' w/650 sks cwc. 5 1/2" set at 3792' w/200 sks 60' of 4 1/2"
set at 3840' w/50 sks. Order sand and common cement. Pull pipe. Order 600 sks. Dennis
Hamel. 65/35 poz 10% gel, 800# hulls. Halliburton Cement Co. Bill's Tank Service,
Keller Tank Service.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30PM Day: 18 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3740' w/5 sks common cement on sand
w/bailer. Recovered 1250' of 5 1/2" casing. Ran tubing to 2500'. Pumped 150 sks cement blend.
Laid down 40 joints. Pumped 150 sks cement blend. Laid down 30 joints circulated cement
blend w/50 sks. Laid down tubing squeezed to 300#. Max psi close in 150# psi. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
1-17-90

JAN 17 1990

Remarks: _____
(If additional description is necessary, use BACK of this form.)

do not disturb this plugging.

INVOICED
JAN 24 1990

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

DATE _____

INV. NO. 2703
10-18 FEB 09 1990