

15-163-01938-0000

6 100303

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 6/10/49

NE NE NE , SEC. 18 , T 10 S, R 19 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6273

Lease Name Anderson Well # 1

Operator: Robert R. Price Operating Inc.

County Rooks 125.91

Name & Address Box 470442

Well Total Depth 3874 feet

Tulsa, Ok. 74147

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 235

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Operator License Number

Address

Company to plug at: Hour: 3:00 PM Day: 24 Month: Sept Year: 19 87

Plugging proposal received from Operator

(company name) (phone)

were: Order 450 sks Econolite Cement and 700 lbs. Hulls.

7" casing set at 3873', Dakota formation squeezed to surface.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:00 PM Day: 24 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Shoot four (4) holes at 1620'. Hook onto 7" casing and pump

down with 50 sks cement. Then, pump down casing with 400 sks cement mixed with 700 lbs Hulls. Maximum pump pressure and shut in pressure was 750 Psi.

Cemented by B. J. Titan

11-12-87

Remarks: (if additional description is necessary, use BACK of this form.)

observe this plugging.

Signed David Wann (TECHNICIAN)

DATE 11-12-87

BY NO. 18842

David Wann