

9-24-87 15-163-30215-0000

6 100302

API NUMBER 15- 7/12/66

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NE, SEC. 18, T 10 S, R 19 W/E
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6273

Lease Name Anderson Well # 9

Operator: Robert R. Price Operating Inc.
Name & Address: Box 470442
Tulsa, Ok 74147

County _____ Rooks 123.70
Well Total Depth 3806 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor _____ Operator _____ License Number _____

Address _____

Company to plug at: Hour: 12:30 PM Day: 24 Month: Sept Year: 19 87

Plugging proposal received from Robert Price

(company name) _____ Operator _____ (phone) _____

were: Order 250 sks Econolite and 500 lbs Hulls.
5 1/2" casing set at 3800', squeezed from 1100' to surface.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 24 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Shoot four (4) hole at 1645', hook onto 5 1/2" casing and pump down 15 sks cement. Then, pump 235 sks cement mixed with 500 lbs of Hulls.

Maximum pump pressure and shut in pressure of 400 Psi. Cemented by B. J. Titan.

RECEIVED
STATE CORPORATION COMMISSION

10-23-87
OCT 23 1987

Remarks: (If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

Signed David Wann (TECHNICIAN)

DATE 10-26-87

David Wann

INV. NO. 186 ~~72~~ 09-24