

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01953-00-00
Spot: SWSESW Sec/Twnshp/Rge: 18-10S-19W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SCOGGINS Well Number: 4
County: ROOKS Total Vertical Depth: 3830 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3830 200 SX CMT
Surface Casing Size: 8.625 feet: 1636 625 SX CMT

\$12448

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2003 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf casing at 1550'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/09/2003 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2700' - spotted 210 sxs 60/40 pozmix - 10% gel with 400# hulls mixed in cement to circulate at surface.
POOH with tubing - squeezed 16 sxs 60/40 pozmix - 10% gel down 5 1/2" casing.
Circulated cement to surface out of 8 5/8" surface pipe. Shut in.
Squeezed 5 1/2" casing with additional cement to Max. P.S.I. 500#.

RECEIVED
10-30-03
OCT 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

10
INVOICED

DATE 10-30-03

NO. 2004060694

SKELLY OIL CO.

#4

22-18-10-19W
SCROGGINS AVE SW SE SW

Contr.

ROOKS

County

E 2230

Comm. 5-14-49

Comp. 6-24-49

IP 165 BOPD. PHY POT

Tops	Depth	Datum
HEEB	3438	- 1208
LANS	3475	- 1245
ARB	3795	- 1565
T.D.	3830	- 1600

Casing
 8" 1636 PERF 3795-99
 5" 3830 1 GO & 4 GWPH
 SQZ
 PB 3797
 PERF 355, 3790-95
 AC ID. 3000
 SWB 20 B0/3 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS