

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21,790-0000

NE, Sec. 19, T 10 S, R 19 W/E

660 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Lease Name Berland Well # 1

Operator: Krueger, Harold, Co.  
Name &  
Address P.O. Box 247, Natoma, Mo. 67651

County Rooks

Well Total Depth 3810 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Co. License Number 81

Address 1720 K.S. Bldg, Wichita, Mo. 67202

Company to plug at: Hour: 2:00 AM Day: 13 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Bill Ayres

(company name) Red Tiger Drilling Co. (phone) 316-263-2371

were: Order 160 sacks 50 pro mix - 4% Sol. - 3% lat. Cl. & 8 5/8" plug. Spot w/drill stem w/ heavy mud between all plugs. 1st plug C 3810' w/ 20 sacks, 2nd plug C 1630' w/ 80 sacks, 3rd plug C 350' w/ 40 sacks, 4th plug - solid bridge of hulls & plug C 40' w/ 10 sacks. Circulate 10 sacks in rat hole.

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 AM Day: 13 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 288' S.P. uc. w/ 175 sacks common - 2% Sol. - 3% lat. Cl.

Ordered 160 sacks 50 pro mix - 4% Sol. - 3% lat. Cl. & 9 5/8" plug. Spot w/drill stem w/ heavy mud between all plugs. 1st plug C 3810' w/ 20 sacks, 2nd plug C 1630' w/ 80 sacks, 3rd plug C 350' w/ 40 sacks, 4th plug - solid bridge of hulls & plug C 40' w/ 10 sacks. Circulate 10 sacks in rat hole.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
10-19-82  
OCT 19 1982

I hereby certify that the above plugging instructions were given with the results stated and that I (did / did not) observe this plugging.

Signed [Signature]  
(TECHNICIAN)

INVOICED  
DATE 11-16-82  
INV. NO. 1588-w

D