

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5056
Name: F.G. Holl Company, L.L.C.
Address 1: 9431 E. Central, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Franklin R. Greenbaum
Phone: (316) 684-8481, Ext. 206

API No. 15 - 047-21,289-0000
If pre 1967, supply original completion date: _____
Spot Description: SW
SE SE NW NE Sec. 13 Twp. 24 S. R. 17 East West
4.125 Feet from North / South Line of Section
4.455 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Edwards
Lease Name: HAWLEY Well #: 9-13

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 330' Cemented with: 225sx Sacks
Production Casing Size: 4-1/2" Set at: 4441' Cemented with: 225sx Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 2107 (G.L. / K.B.) T.D.: 4450 PBTD: None Anhydrite Depth: 1080'
(Stone Corral Formation)
Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)
Proposed Method of Plugging (attach a separate page if additional space is needed):

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 23 2009

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
If ACO-1 not filed, explain why:

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Mr. Rob Long
Address: 701 E. Santa Fe, Box 308 City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410
Proposed Date of Plugging (if known): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/22/2009 Authorized Operator / Agent: _____

Loveness Mpanje
Loveness Mpanje

(Signature)

Dist 1
AKT

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HAWLEY #9-13

Located: SW SE NW NW, Section 13-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl Estate

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 15, 1987

COMPLETED: September 21, 1987

TOTAL DEPTH: 4450'

| <u>LOG</u> | <u>CASING RECORD</u> |
|---------------------------------|---|
| 0 - 90 Surface Soil and Sand | Ran 8 joints 8 5/8", 23# new casing. 318.28' pipe set at 330' K.B. |
| 90 - 190 Clay, Shale | Cemented with 225 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 7:30 PM, 9-15-87, by B. J. Titan. |
| 190 - 333 Shale | |
| 333 - 680 Shale, Sand, Red Beds | |
| 680 - 1080 Shale, Lime | |
| 1080 - 1098 Anhydrite | |
| 1098 - 4405 Lime and Shale | |
| 4405 - 4450 Viola | Ran 104 joints 4 1/2", 10.5# used casing. 4432.30' pipe set at 4441.30' K.B. Cemented with 125 sacks Light cement with 250 gallons mud flush ahead, followed with 100 sacks 50/50 Pozmix with F. G. Holl regular addi- tives. Plug down at 6:05 AM, 9-21-87, by B. J. Titan. |

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 23 2009

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1/4° at 2050'
2° at 4450'



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

October 05, 2009

Re: HAWLEY #9-13
API 15-047-21289-00-00
13-24S-17W, 4125 FSL 4455 FEL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 3, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888