

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20568-00-00
Spot: SESE Sec/Twnshp/Rge: 4-1S-26W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: SUMNER Well #: 2
County: DECATUR Total Vertical Depth: 3570 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	313	0	w/unknown sxs cmt
PROD	4.5	3568	0	450 SX

116.03

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2009 1:00 AM
Plug Co. License No.: 34093 Plug Co. Name: SUMMIT WELL SERVICE LLC
Proposal Rcvd. from: ROLAND NYP Company: HERMAN L. LOEB, LLC Phone: (785) 737-3242

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2009 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 313' w/unknown sxs cement.
4 1/2" production casing set at 3568' w/450 sxs cement.
Junk in the hole at 2630'.
Ran tubing to 2300' - pumped 180 sxs cement with zero hulls - cement to surface.
Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 20 sxs cement.
Max. P.S.I. 300#.
Connected to 8 5/8" surface casing - pumped 60 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3446	3448		
3424	3426		
3399	3402		
3360	3368		
3326	3330		

RECEIVED
KANSAS CORPORATION COMMISSION
SEP - 8 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: ALLIED CEMENTING COMPANY-TICKET #44257.

Plugged through: TBG

DATE 10-2-09
INV. NO. 2010060346

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

Form CP-2/3

SEP 04 2009

PKT

