

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-21134-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 31-32S-6E  
321 feet from S Section Line, 919 feet from E Section Line  
Lease Name: WERNER 'B' Well #: 3  
County: COWLEY Total Vertical Depth: 3140 feet

Operator License No.: 5394  
Op Name: ABDERHALDEN, R. R.  
Address: 510 HARDAGE CENTER 100 S MAIN  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	165		70 SX
PROD	4.5	3139	1676	75 SX

102.05

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/04/2009 8:00 AM  
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.  
Proposal Rcvd. from: DWAIN STOUT Company: R R ABDERHALDEN Phone: (316) 262-3411

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/06/2009 11:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/2-3/8" TUBING @ 3,074', CIRCULATED HOLE CLEAN. DUMPED 35 SXS SAND, TAGGED @ 3,025'. DUMP BAILED 5 SXS CLASS A CEMENT ON TOP. TAGGED SAND AND CEMENT @ 2,980. CUT CASING @ 1,676', LAYED DOWN 4-1/2" CASING. RIH W/WORKSTRING @ 348', R.R.A. MIXED & PUMPED 117 SXS CLASS A COMMON CEMENT TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-6-2009, 11:30 AM. NO TICKET #.

Perfs:

Top	Bot	Thru	Comments
3076	3084	CSG	

INVOICED

DATE 10-7-09  
INV. NO. 2010060351

RECEIVED  
SEP 03 2009  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)