

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20879-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 8-2S-33W
2400 feet from S Section Line, 1375 feet from E Section Line
Lease Name: BEARLEY UNIT Well #: 1
County: RAWLINS Total Vertical Depth: 4275 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 260

138.94

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/03/2009 9:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 09/03/2009 10:45 PM KCC Agent: DAVID WANN

Actual Plugging Report:
1st. Plug at 2860' w/25 sxs.
2nd. Plug at 2100' w/100 sxs.
3rd. Plug at 310' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:
INVOICED
10-7-09
2010060352

RECEIVED
KANSAS CORPORATION COMMISSION
SEP - 8 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

(TECHNICIAN)

CM

PKT