

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-21048-00-00  
Spot: NWSESWSW Sec/Twnshp/Rge: 6-3S-26W  
365 feet from S Section Line, 870 feet from W Section Line  
Lease Name: WENTZ Well #: 6-1  
County: DECATUR Total Vertical Depth: 3870 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC  
Address: 1889 200TH AVE  
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	263	0	170 SX
T1	2.375	3825		125.78
PROD	4.5	3869	0	170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2009 10:30 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: TERRY GARRISON Company: RON'S OIL OPERATIONS INC. Phone: (785) 421-4240

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls - 10 sxs gel.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2009 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 263' w/170 sxs cement.  
4 1/2" production casing set at 3869' w/170 sxs cement.  
Port collar was not cemented.  
Perforated production casing at 2215' and 1500'.  
Ran tubing to 3730' - pumped 7 sxs gel - followed with 75 sxs cement mixed with 400# hulls.  
Pulled tubing to 2200' - pumped 150 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 4 1/2" production casing - pumped 20 sxs cement.  
Connected to 8 5/8" surface casing - pumped 50 sxs cement.  
Max. P.S.I. 75#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3761	3765		
3734	3736		

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP - 8 2009  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 10-7-09  
ITEM NO. 2010060353

Remarks: ALLIED CEMENTING COMPANY-TICKET #43671.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

CM

PKT

RON'S OIL OPERATIONS  
PENOKEE KS 67659-2036

**6-03S-26W**  
365'FSL & 870'FWL, SEC  
KANSAS

#6-1 WENTZ

City: DECATUR

Spot: NW SE SW SW API 15-039-21048

Site: 1-1/2 S & 5 W OF NORCATUR KS

Lat/Long: 39.81463 -100.28845

Field: PLUM CREEK EXT (1/2 NW)

OIL

FR: 02/20/2008 Spd: 03/04/2008 Drig Cp: 03/11/2008 Issued: 08/25/2008 Revised: 08/25/2008


Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

**IP Status:**

**OIL, LKC, INTV NA, 6/1/2008**

**Contr: WW DRILLING #4**

**Elev: 2640 GL**

**Formation Tops: (L-Log, S-Sample, D-Driller)**

NO TOPS RPTD

ERTD

3850 -1210

**Csg: 8-5/8" 250+ (ALT 2), PROD CSG NA**

**Find:**

COMMENT: PROPOSED START 2/25/2008; MI &  
RURT 3/4/2008

NO CORES

DSTS TAKEN - DETAILS NA

**Comp Info: TRGT ZN: ARB (OIL), PTD 3850 (ARB),**

**MICT (3/24/2008) - CO, PF (LKC) INTV NA, GSO,**

**POP, OIL WELL (POTENTIAL NOT RPTD), 6/1/2008**

- TIGHT HOLE - NO OTHER INFO AVAILABLE -

TEMP COMP 8/25/2008