

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-01702-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 11-26S-6W  
3389 feet from S Section Line, 2048 feet from E Section Line  
Lease Name: KREHBIEL A Well #: 1  
County: RENO Total Vertical Depth: 3995 feet

Operator License No.: 33324  
Op Name: ALLAM PRODUCTION, INC.  
Address: PO BOX 2325  
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	251		
PROD	5.5	3993		

129.84

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: W R ALLAM Company: ALLAM PRODUCTION Phone: (620) 465-2337

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/01/2009 3:30 PM KCC Agent: B. J. HOPE

Actual Plugging Report:  
8/31/09 SANDED BACK TO 3932' PLACED 5 SXS OF CEMENT ON TOP OF SAND. PERFORATED CASING AT 800' AND AT 400'. 9/1/09 RAN TUBING IN SPOTTED 35 SACKS AT 800' WAITED 1.5 HOURS AND TAGGED AT 450'. AT 400' CIRCULATED TO SURFACE WITH 135 SXS OF CEMENT. 9/2/09 CUT OFF HEAD TO VERIFY CEMENT ON BACKSIDE, GOOD CEMENT ON BOTH SIDES. OPEN HOLE=NO PERFS

Perfs:  
**INVOICED**  
DATE: 10-12-09  
INV. NO. 2010060364

**RECEIVED**  
**SEP 10 2009**  
**KCC WICHITA**

Remarks: BASIC ENERGY SERVICES - 60/40 4% GEL - POS MIX WITH 3% CC TICKET #1718-05344 GPS LAT. 37.80134, LONG. -97.94267

Plugged through: TBG

District: 02 Signed B. J. Hope (TECHNICIAN)

JK

PKT