

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20580-00-01
Spot: SWNWSESW Sec/Twnshp/Rge: 20-31S-21W
750 feet from S Section Line, 1490 feet from W Section Line
Lease Name: MOORE Well #: 7
County: CLARK Total Vertical Depth: 4917 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	651		WITH 550 SX CMT
COND	16	47		
PROD	5.5	4850	0	WITH 250 SX CMT

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 08/17/2009 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2009 11:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

2 7/8" TBG STUCK IN HOLE FROM T.D. TO SURFACE W/BALLED UP CABLE & DOWNHOLE SUBMERSIBLE PUMP. 8/17/09: 1ST PLUG ATTEMPTED TO SHOOT-OFF TBG @ 1040', 850', & 650'. STILL STUCK IN 5 1/2". TIED ONTO 2 7/8" TBG & PUMPED 10 SX GELLED WATER TO LOAD HOLE. NO CIRCULATION. CHANGED OVER TO CMT & PUMPED 200# HULLS & 300 SX CMT. NO FLUID BACK TO SURFACE. SHUT DOWN. CLEANED TBG W/12 BBL FRESH WATER. 8/21/09: 2ND PLUG HOOKED TO 2 7/8" TBG, PUMPED 1/2 BBL CMT. PRESSURED TO 600#. 3RD PLUG HOOKED TO 5 1/2" X 8 5/8" ANNULUS. PUMPED 3 BBL CMT. PRESSURED TO 600#. 4TH PLUG RAN 1" BESIDE 2 7/8" IN 5 1/2" TO 15'. FILLED CASING W/1/2 BBL CMT.

Perfs:

Top	Bot	Thru	Comments
4492	4740		

RECEIVED
SEP 14 2009
KCC WICHITA

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

DATE 10-12-09
INV. NO. 2010060365

Plugged through: TBG

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
SEP 10 2009
KCC DODGE CITY