

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19278-00-01
Spot: NESESW Sec/Twnshp/Rge: 13-32S-4E
987 feet from S Section Line, 2938 feet from E Section Line
Lease Name: LIERMAN Well #: 1
County: COWLEY Total Vertical Depth: 3028 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	200		
T1	2.375	2980		
PKR		2980		
PROD	5.5	3008	1421	

98.41

Well Type: EOR UIC Docket No: E23638.2 Date/Time to Plug: 08/27/2009 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT WELL PLUGGING Phone: (580) 763-7740

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 08/27/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WIRELINE & SET CIBP @ 2950', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 1421', LAYED DOWN 5-1/2" CASING. RIH W/TBG @ 250' CONSOLIDATED MIXED & PUMPED 133 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-27-2009, 5:00 P.M.

Perfs:

Top	Bot	Thru	Comments
3008	3028		

INVOICED
DATE: 10-12-09
INV NO: 2010060366

RECEIVED
SEP 10 2009

Remarks: CONSOLIDATED TICKET #23012. GPS: LAT: 37.26184, LONG: -096.94339

KCC WICHITA

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

JK

PCT