

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23289-00-00
Spot: SESWSE Sec/Twnshp/Rge: 13-32S-4E
649 feet from S Section Line, 1636 feet from E Section Line
Lease Name: ROWE Well #: 13-1
County: COWLEY Total Vertical Depth: 3052 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment	
SURF	8.625	211			99.19
PROD	4.5	3051	762	TOP OF CEMENT @ 1480'	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2009 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT WELL PLUGGING Phone: (580) 763-7740

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 09/01/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WIRELINE & SET CIBP @ 1600', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 762', LAYED DOWN 4-1/2" CASING. RIH W/TBG @ 260' CONSOLIDATED MIXED & PUMPED 91 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 9-1-2009, 5:00 PM.

Perfs:

Top	Bot	Thru	Comments
3010	3016	CSG	2 PER FOOT
2998	3006	CSG	2 PER FOOT
2988	2999	CSG	2 PER FOOT

INVOICED
DATE: 10-12-09
INV. NO. 2010060366

RECEIVED
SEP 10 2009
KCC WICHITA

Remarks: CONSOLIDATED CEMENT TICKET #23063. GPS: LAT: 37.26087 LONG. -096.93892

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT

JK