

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23399-00-00
Spot: NESWSE Sec/Twnshp/Rge: 13-32S-4E
871 feet from S Section Line, 1646 feet from E Section Line
Lease Name: ROWE TWIN Well #: 1-A
County: COWLEY Total Vertical Depth: 2393 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment	
SURF	8.625	217			77.77
PROD	4.5	2393	1327	TOP OF CEMENT @ 1640'	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2009 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT WELL PLUGGING Phone: (580) 763-7740

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 09/01/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIRCULATED WORKSTRING @1327, CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A 3% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1,212'. CUT CASING @ 1327', LAYED DOWN 4-1/2" CASING. RIH W/TBG @ 270' CONSOLIDATED MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 9-1-2009, 5:00 P.M.

Perfs:

Top	Bot	Thru	Comments
2346	2349	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 17 2009
CONSERVATION DIVISION
WICHITA, KS
INVOICED

Remarks: CONSOLIDATED CEMENT TICKET #23034. GPS: LAT 37.26148, LONG: -96.93895

DATE 10-12-09
INV. NO. 2010060366

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

JK

JK