

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20079-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 32-16S-19W
990 feet from N Section Line, 4950 feet from E Section Line
Lease Name: SCHMIDT A Well #: 4
County: RUSH Total Vertical Depth: 3832 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	182		WITH 160 SX CMT CIRCULATED
DVT		1221		WITH 375 SX CMT DID NOT CIRCULATE
PROD	4.5	3794	0	WITH 75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/02/2009 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: PUMP 40 SX CMT WITH HULLS MIXED IN. DISPLACE TO BOTTOM WITH GEL. RUN BOND LOG. RAN GAMMA RAY. IF CMT IS HIGH ENOUGH ON 2ND STAGE, RUN CMT FROM 1200'-0'. PRESSURE 8 5/8" X 4 1/2" TO 500 PSIG WITH CMT.
124.54

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2009 12:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 300# HULLS MIXED IN 40 SX CMT. DISPLACED WITH 18 SX GEL FOLLOWED BY 20 BBL WATER. MAXIMUM PUMP PRESSURE 1000 PSIG. SHUT IN PRESSURE 600 PSIG. RAN BOND LOG. CMT FROM 1170' -110'. RAN GAMMA RAY LOG, FORMATIONS HAVE NOT MOVED. SWABBED 4 1/2" CASING DOWN TO 1200' FILLED 4 1/2" CASING FROM 1200' TO 0' WITH 75 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3794	3832	OH	

RECEIVED
SEP 14 2009
KCC WICHITA

INVOICED

DATE 10-12-09
INV. NO. 20100 60368

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG


District: 01

RECEIVED

SEP - 9 2009

KCC DODGE CITY

Signed



(TECHNICIAN)