

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23609-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 23-27S-21E
200 feet from N Section Line, 200 feet from W Section Line
Lease Name: INMAN Well #: 4-23B
County: BOURBON Total Vertical Depth: 808 feet

Operator License No.: 33397
Op Name: RUNNING FOXES PETROLEUM INC.
Address: 7060 S TUSCON WAY STE B
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20	0	

35 -

Well Type: Oil DH KCC UIC Docket No: _____ Date/Time to Plug: 08/27/2009 9:30 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, LLC Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 808' THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 808', A 50' CEMENT PLUG AT 500', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2009 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO 808'. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 12 SACKS OF CEMENT WERE PUMPED TO 808'. THE PIPE WAS PULLED TO 500' AND 12 SACKS OF CEMENT WERE PUMPE TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
SEP 08 2009
KCC WICHITA

RECEIVED
KCC DISTRICT #3

SEP - 2 2009 CPT
CHANUTE, KS

INVOICED
DATE: 10-12-09
INV. NO. 2010060357

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PT