

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23613-00-00
Spot: NWNWNWSW Sec/Twnshp/Rge: 6-27S-22E
2450 feet from S Section Line, 190 feet from W Section Line
Lease Name: BECK Well #: 12-6B
County: BOURBON Total Vertical Depth: 888 feet

Operator License No.: 33397
Op Name: RUNNING FOXES PETROLEUM INC.
Address: 7060 S TUSCON WAY STE B
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20	0	

35

Well Type: OLDH recept UIC Docket No: _____ Date/Time to Plug: 08/26/2009 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, LLC Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 888'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 08/26/2009 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:
1" PIPE WAS RAN INTO THE WELL TO T.D.. THE WELL WAS GELLED FROR BRIDGING PURPOSES. 12 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO T.D.. THE 1" PIPE WAS PULLED TO 500' AND 12 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 500'. THE 1" PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:
RECEIVED
SEP 08 2009
KCC WICHITA
RECEIVED
KCC DISTRICT #3
SEP = 1 2009 CPT
CHANUTE, KS
INVOICED
DATE 10-12-09
INV. NO. 2010060357

Remarks:
Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

[Handwritten initials]