

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23463-00-00
Spot: SENWNW Sec/Twnshp/Rge: 10-30S-4E
4078 feet from S Section Line, 4187 feet from E Section Line
Lease Name: DAVES UNIT Well #: 34
County: COWLEY Total Vertical Depth: 2904 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	209		150 SXS CMT
PROD	5.5	2904		100 SXS CMT

94.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2009 8:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ROBBIE WILLIAMS Company: STELBAR OIL CORPORATION INC Phone: (316) 641-0024

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2009 1:40 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2803', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 30 SXS CLASS A 3% CC, 1% GLE AND DISPLACED IN CASING. WAITED 2-HOURS TAGGED CEMENT @ 2612'. 8-12-2009, RIH ON WIRELINE W/CIBP SET @ 270'. CUT 5-1/2" CASING @ 242', LAYED DOWN 5-1/2" CASING. RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 90 SXS CLASS A CEMENT TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-12-2009 1:40 PM. CONSOLIDATED CEMENT TICKET #s 21243 & 21246.

Perfs:

Top	Bot	Thru	Comments
2803	2805	CSG	

INVOICED
DATE 10-12-09
INV. NO. 2010060358

RECEIVED
SEP 03 2009
KCC WICHITA

Remarks: COLLAPSED CASING @ 1230'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

JK

JK