

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21438-00-00
Spot: E2SWNE Sec/Twnshp/Rge: 26-8S-18W
3300 feet from S Section Line, 1377 feet from E Section Line
Lease Name: PAUL DECHANT Well #: 1
County: ROOKS Total Vertical Depth: 3414 feet

Operator License No.: 34179
Op Name: THOMAS M. BROWN LLC
Address: PO BOX 250
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	146	0	w/105 sxs cmt
T1	2.375	3430		
PROD	4.5	3413	0	w/unknown sxs cmt

110.96

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/02/2009 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JAKE BROWN Company: THOMAS M. BROWN LLC Phone: (785) 434-7141

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Sanded back to 3000'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2009 12:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Bottom sanded off to 3000'.
Bad casing 800' - 1000'. Ran 3 1/2" liner to 2400' - unable to get below.
Parted liner at 1600' - decided to P/A.
Ran tubing to 1485'. Allied pumped 100 sxs neat.
Pulled tubing to 800'. Allied pumped 70 sxs neat - circulated cement.
PTOH. Pumped 30 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#.
Topped off with 15 sxs cement.
Hooked up to backside - pumped 50 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.
Note: 3 1/2" - 1600' - 2400' left in the hole.

Perfs:

Top	Bot	Thru	Comments
3413	3433		
3356	3360		
3333	3337		
3314	3320		
3259	3262		
3247	3252		

INVOICED
DATE 10-12-09
INV. NO. 2010060359
RECEIVED
SEP 04 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed R. Williams
(TECHNICIAN)

CM

Form CP-2/3

SEP 03 2009

95

THE GENE BROWN CO.

REPLACEMENT CARD:

407 S. MAIN

#1 PAUL DECHANT

26-8-18W

PLAINVILLE, KS. 67663

660' FSL &

CONTR LAWBANCO DRILLING INC.

CTY ROOKS

1377' FEL, NE/4

GEOL

FIELD DOPITA WEST

E 1993 KB CM 9/26/81 CARD ISSUED 1/7/82 IP P 15 BO & 170 BWPD

LKC 3247-3360 OA

ARB 3413-3433

API 15-163-21,438

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
TOP		2908	- 915
KH		3001	-1008
QH		3057	-1064
HEEB		3117	-1124
TOR		3139	-1146
LANS		3159	-1166
B KC		3385	-1392
ARB		3412	-1419
RTD		3414	-1421
DDTD		3433	-1440

8-5/8" 146/105sx, 4 1/2" 3413

NO DST'S
 MICT - CO, (ARB OH) DD 3433 TD, AC
 1000 G (28%), SWB DWN W/SO, SET RBP @
 3400, PF (LKC) 8/3356-60, 12/3314-20,
 8/3333-3337, AC 1000 G (15%), SWB
 DWN, SET RBP @ 3300, PF (LKC) 6/
 3259-62, 10/3247-52, AC 1000 G (15%),
 SWB DWN, PULL PLUGS, POP, P 15 BO &
 170 BWPD, 10/27/81, COMMINGLED

INFO RELEASED: WAS OIL WELL - TIGHT HOLE - 1/28/82

INDEPENDENT OIL & GAS SERVICE WICHITA, KANSAS