

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-00997-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 5-34S-6E
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: RAHN UNIT 1 Well #: 4
County: COWLEY Total Vertical Depth: 2885 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	100		
LI	4.5	350		93.76
PROD	5.5	2862	350	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2009 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO LLC Phone: (316) 218-1822

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2009 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 1,600', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 350', LAYED DOWN 5-1/2" CASING AND 4-1/2 LINER. RIH W/TBG @ 350', CONSOLIDATED MIXED & PUMPED 160 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-12-2009 @ 3:00 PM. CONSOLIDATED CEMENT TICKET #23555.

Perfs:

INVOICED
DATE 10-12-09
INV. NO. 2010060362

RECEIVED
SEP 03 2009
KCC WICHITA

Remarks:
Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

JK

PK