

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-02089-00-00  
Spot: SENESE Sec/Twnshp/Rge: 6-34S-6E  
1717 feet from S Section Line, 487 feet from E Section Line  
Lease Name: RAHN UNIT 1 Well #: 3  
County: COWLEY Total Vertical Depth: 2893 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment	
SURF	10.75	164		200 sx	94.02
PROD	6	2864		200 sx	79.98

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2009 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO LLC Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 08/14/2009 10:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 1,600', DUMP BAILED 2 SXS CEMENT ON TOP. RIH W/1" TBG ON BACKSIDE OF 6" AND INSIDE OF 10" @ 47', CONSOLIDATED MIXED & PUMPED 15 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN 1" TBG. RIH W/WORKSTING INSIDE 6" CASING @ 330', CONSOLIDATED MIXED & PUMPED 55 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED PLUG DOWN 8-14-2009 @ 10:30 AM. CONSOLIDATED CEMENT TICKET # 23556.

Perfs:

Top	Bot	Thru	Comments
2119	2122		CSG

INVOICED  
DATE 10-12-09  
INV. NO. 2010060363  
2010060362  
RECEIVED  
SEP 03 2009  
KCC WICHITA

Remarks:  
Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

JK

PPT