

To: 6 041002
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-8
API NUMBER 15- 163-21,529 - 0000
S NE SW, SEC. 20, T 10 S, R 19 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033
Operator Name: Murfin Drilling Co. Case Name Berland Well # A-2-20
Address: 250 N. Water S. 300
Wichita, Ks. 67202
County Rooks
Well Total Depth 3870 feet
Operator Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 214 cwc

RECEIVED
STATE CORPORATION COMMISSION
1-18-89
JAN 18 1989
CONSERVATION DIVISION
Wichita, Kansas

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement License Number _____

Address Hays, Ks.

Company to plug at: Hour: 9:00AM, Day: 8 Month: Dec Year: 19 88

Plugging proposal received from John Niernberger

(company name) Murfin Drilling (phone) _____

were: 5 1/2" casing set at 3869' w/150 sks. Top perf at 3761'. D.V. at 1666'. Ordered
200 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 12:15Pm Day: 8 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 190 sks cement w/1/4# F.C. plus 5 sks Hulls
mixed in cement. Max 1000#. S.I. 1000# psi. Pumped in 8 5/8" casing 5 sks cement w/1/4# F.C.
Max 500# S.I. 500# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

JLS

Dennis L. Hamel

INVOICED
DATE 1-19-89
NO. 23715