

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21193-00-00
Spot: CNENWSE Sec/Twnshp/Rge: 21-10S-19W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: LARGENT DICK Well Number: 1-21
County: ROOKS Total Vertical Depth: 3747 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 3 1/2" 78
Surface Casing: Size 8.625 feet: 222 170 SX CMT
Production: Size 5.5 feet: 3746 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/08/2002 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 250 sxs cement - 13 sxs gel and 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/08/2002 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 222' w/170 sxs cement. 5 1/2" casing at 3746' w/200 sxs cement.
D.V. Tool at 2632' w/600 sxs cement.
Tied to 5 1/2" casing - spotted 30 sxs cement with 200# hulls, 13 sxs gel and 300# hulls.
Squeezed 170 sxs cement with 100# hulls.
Max. P.S.I. 800#. S.I.P. 300#.
Total of 200 sxs 60/40 pozmix - 10% gel - 13 sxs gel and 600# hulls.

RECEIVED
11-19-02
NOV 19 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger H. Moses
(TECHNICIAN)

INVOICED

DATE 11-20-02

WV. NO. 2003060838

Form CP-2/3

NOV 15 2002

