

9-2
4- 062674

D-21,123

API number: 15-163-20,250 ~~000~~ /

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NW /4 SEC. 27 , 10 S , 19 W
990 feet from N section line
990 feet from W section line

Operator license# 6412

Lease O'Brien well # 1

Operator: Sid Tomlinson

County Rooks

Address: 1802 Wildwood Drive
Oklahoma City, OK 74075
405-372-2833

Well total depth 3776 feet ^{122.72}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cementing Co., Inc. License# -

Address: Box 342 - Plainville, Kansas 67663 - 913-434-2812

Company to plug at: Hour: 8:00A.M Day: 2 Month: September Year: 92

Plugging proposal received from: James R. Line

Company: Sid Tomlinson Phone: 913-483-4092

Were: 4 1/2" casing with 1450'-cement to surface with 300 sks. cement.
Pumped in 100 sks. - 2% gel. followed with 4 sks. hulls. 125 sks.
with 60/40 posmix - 8% gel. with 20 sks. common with 2% gel.

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30P.M., Day: 2, Month: September, Year: 92

Actual plugging report: 8 5/8" @ 217' w/160 sks. 4 1/2" @ 3691' w/150
sk. Top perf. @ 3776'. Plugged bottom with sand and 5 sks. cement to
3750'. Pump in 4 1/2" casing with 245 sks. cement w/1500 P.S.I.
Max. pressure on 4 1/2" - 1500 P.S.I. Shut in @ 1500 P.S.I.
Total sack 245 cement.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES 1620 NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation: 2149
I did X did not[] observe the plugging. Gilbert G. Scheck

RECEIVED
STATE CORPORATION COMMISSION
9-16-92
SEP 16 1992
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-7-92
INV. NO. 36345

(agent)