

15-163-20273-0001 *R*

6040454

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____

NW-SW-SE, SEC. 27, T. 10 S, R. 19 W

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name Sutor Well # 1

Operator: Liberty Oper & Comp.

County Roosar 119.83

Name & Address Plainville, Kansas

Well Total Depth 3687 feet

67663

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 284 w/circ cmt

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Emty. License Number _____

Address Russell, Kansas

Company to plug at; Hour: 8:00 AM Day: 23 Month: 9 Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casings (phone) _____

were: _____

4 1/2" csg set @ 3686' w/ 150 sx cmt. hp Perfs @ 3404'
Rhig bottom w/sand to 3350' & cmt 4 sx. Res 2200' of
4 1/2" csg.

Ordered 200 sx 6 3/4 poz - 6 3/4 gel; 25 sx gel, Shulls &

8 5/8" w/plug Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 AM Day: 23 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT pumped in 4 1/2" csg -> 50 sx cmt w/

shulls; -> 15 sx gel w/shulls, -> 100 sx cmt/shulls, ->

10 sx gel w/shulls -> Rel plug, -> 50 sx cmt.

Shut-in P.S.I. 400#

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-14-85

INV. NO. 10449

RECEIVED

OCT 7 1985

Signed Dennis L. Hamel
(TECHNICIAN)

16
10-4-85
mgg