

9-3

4-060430

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,231-0000

E2 NW NE /4 SEC. 29, 10 S, 19 W  
4620 feet from S section line  
1650 feet from E section line

Operator license# 4026

Lease Largent-Dick well # 4

Operator: Ash-Bie Oil Company

County Rooks

Address: P.O. Box 194  
Ellis, Kansas 67637

Well total depth 3791 feet <sup>123.20</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 225 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Shields Drilling Company, Inc. License# 5655

Address: Shields Building, Russell, Kansas 67665

Company to plug at: Hour: 1:00P.M. Day: 3 Month: September Year: 93

Plugging proposal received from: Burt Beery

Company: Shields Drilling Company, Inc. Phone: 913-483-3141

Were: Order 225 sxs. 60/40 posmix - 6% gel with 1/4# flocele per. sx.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 4:00P.M., Day: 3, Month: September, Year: 93

Actual plugging report:  
1st. plug st 3758' with 25 sxs. - Arbuckle 3768'.  
2nd. plug at 1645' with 25 sxs. - Anhydrite 1627' - 1659'.  
3rd. plug at 940' with 100 sxs. - Dakota 638' - 938'.  
4th. plug at 275' with 40 sxs. - Surface pipe to 225'.  
5th. plug at 40' with 10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES X , CALC      , NO      Dakota plug: YES X NO       
Plugged through TUBING      , CASING      . Elevation: 2213

I did[      ] / did not[ X ] observe the plugging.

DATE SEP 17 1993

INV. NO. 38684

[Signature]  
DT (agent)

RECEIVED  
STATE CORPORATION COMMISSION  
9-13-93  
SEP 13 1993  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED