

7-11

4-032071

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-163-00,984-0001

NW NW SW /4 SEC. 30, 10 S, 19 W
2310 feet from S section line
4950 feet from E section line

Operator license# 31435

Lease: Schonthaler Well # 4

Operator: Schonthaler Limited Liability Co.

County: Rooks

Address: P.O. Box 370782
Denver, CO 80237-0782

Well total depth 3820 ^{124.15} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 207 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 11 Month: July Year: 1995

Plugging proposal received from: Carl Zimmerman - Marion J. Schmidt

Company: Manta Petroleum Company - K.C.C. Phone: _____

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
7-17-95
JUL 17 1995

Plugging Proposal Received by: Carl Goodrow CONSERVATION DIVISION
Plugging operations attended by agent? All[X], Part[], None[] WICHITA, KS

Completed: Hour: 10:30 A.M., Day: 11, Month: July, Year: 1995

Actual plugging report: 8 5/8" set at 207' cwc. 5 1/2" set at 3819' w/175 sxs. Prod perf at 3775' - 3777'. C.I.B.P. at 3420'. Perf at 3340' - 3343'. Critical area control perfs at 2300' - 1600' - 935'. Mixed and pumped down 5 1/2" - 75 sxs cement with 100# hulls. Displaced to 2300'. Perf casing as above, mixed and pumped down 5 1/2" - 200 sxs cement with 200# hulls to Max. P.S.I. 600#. Close in P.S.I. 200#. Squeezed 8 5/8" with 100 sxs cement with 50# hulls to Max. P.S.I. 800#. Close in P.S.I. 200#. Plug complete.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES _____ NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____, NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

DATE 7-19-95

INV. NO. 43122

7-11