

4 060125 10-28

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION, N2 N2 SE, SEC. 30, T 10 S, R 19 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,123-0000

N2 SE, SEC. 30, T 10 S, R 19 W/E

2310 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Keller "B" Well # 2

Operator: AFG Energy, Inc.

County Rooks 125.12

Name & Address P.O. Box 605

Well Total Depth 3850 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, KS

Company to plug at: Hour: 12:00PM Day: 28 Month: October Year: 19 90

Plugging proposal received from Jack Fox

(company name) Emphasis Oil Operations (phone)

were: Order 215 sxs. 60/40 pos 6% gel 1/2# floccel per sx.

Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXX

Operations Completed: Hour: 12:00PM Day: 28 Month: October Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3800' with 25 sxs. Arbuckle 3808'

2nd plug at 1615' with 25 sxs. Anhydrite 1596-1634'

3rd plug at 935' with 100 sxs. Dakota 635-935'

4th plug at 305' with 40 sxs. Surface pipe to 251'

5th plug at 40' with 10 sxs.

rathole with 15 sxs.

Remarks: Allied Cementing (If additional description is necessary, use BACK of this form.)

XXXXXX (do not) observe this plugging.

NOV 11-8-90 8 1990 CONSERVATION DIVISION

INVOICED

DATE 11-13-90

INV. NO. 29939

H.S.

Signed Herb Deines (TECHNICIAN)

Herb Deines