

6-22 4-031943

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-22,713-0000

NW SE NE /4 SEC. 30 , 10 S, 19 W  
3630 feet from S section line  
990 feet from E section line

Operator license# 30606

Lease Keller 'H' well # 1

Operator: Murfin Drilling Co., Inc.

County Rooks <sup>R<sup>r</sup>KCC</sup> 124.80

Address: 250 N. Market  
Suite 300  
Wichita, Kansas 67202

Well total depth 3840 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 850 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 22 Month: June Year: 94

Plugging proposal received from: Craig - Dennis Hamel

Company: Murfin Drilling and the KCC Phone:                     

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 1/4# flocele - 300# hulls.  
Critical area control shots at 2250' - base salt - 1600' anhy. and  
200' top of 8 5/8".

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:45A.M., Day: 22, Month: June, Year: 94

Actual plugging report: 8 5/8" set @ 850' w/350 sxs. 5 1/2" set at  
3839' w/100 sxs. PBD 3790'. Prod. perfs 3546' - 3788'. CIBP at 3793'.  
Squeezed at 1237' and 880' w/250 sxs. Mix and pumped down 5 1/2" - 275  
sxs. cement blend w/300# hulls. Mixed in to Max. P.S.I. 500#. Close  
in P.S.I. 200#. Squeezed 8 5/8" w/25 sxs. to Max. P.S.I. 200#. Close  
in P.S.I. 200#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD     BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL    

I did not observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
6-30-94  
JUN 30 1994

INVOICED  
DATE JUL 07 1994  
40778  
INV. NO.                     

HTO

CONSERVATION DIVISION  
Wichita, Kansas