

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21,853-0000
NW, Sec. 34, T 10 S, R 19 WE
330 feet from NS section line
1650 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6412

Lease Name Mc. Kennan Well # 1

Operator: Ed Tomlinson
Name & Address P.O. Box 594, Twinfall Id.
83301

County Rooks

Well Total Depth 3750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 275

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Reubin Dalg. Inc. License Number 274

Address P.O. Box 88, Russell, Ks. 67665

Company to plug at: Hour: 1:00 PM Day: 11 Month: 12 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO John Collins

(company name) Reubin Dalg. Inc. (phone) 913-483-5355

were: Order 180 sacks 50 posmix - 4 9/16" gel. - 3 9/16" cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3750' w/ 20 sacks. 2nd plug C 1570' w/ 20 sacks. 3rd plug C 900' w/ 80 sacks. 4th plug C 325' w/ 40 sacks. 5th plug - solid bridge of hulls & plug C 40' w/ 10 sacks. Circulate 10 sacks in rat hole

Signed G. L. Shel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 PM Day: 11 Month: 12 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 275' sp. cas. w/ 170 sacks common - 2 9/16" gel. - 3 9/16" cl.

Ordered 180 sacks 50 posmix - 4 9/16" gel. - 3 9/16" cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3750' w/ 20 sacks. 2nd plug C 1570' w/ 20 sacks. 3rd plug C 900' w/ 80 sacks. 4th plug C 325' w/ 40 sacks. 5th plug C 40' w/ 10 sacks solid bridge of hulls & plug. Circulated 10 sacks in rat hole.

Remarks: Drilled into debris

RECEIVED
STATE CORPORATION COMMISSION
12-21-82
DEC 21 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not) observe this plugging.

INVOICED
DATE 1-31-83
INV. NO. 2268-W

Signed G. L. Shel
(TECHNICIAN)