

4-031688

4-24
15-163-01981-0000

14
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1954

NW NE SW /4 SEC. 35 , 10 S, 19 W
2310 feet from S section line
3630 feet from E section line

Operator license# 30606 Lease Casey well # 2

Operator: Murfin Drilling Co., Inc. County Rooks

Address: 250 N. Water #300 Well total depth 3646 feet ^{118.49}
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 148 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Oakley, Kansas

Company to plug at: Hour: A.M. Day: 24 Month: April Year: 92

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Co., Inc. Phone:

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to production perf. Just stripped rods and tubing.
Perforated at 1455' - anhydrite cwc. 700 sx.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:45P.M., Day: 24, Month: April, Year: 92

Actual plugging report: 8 5/8" set @ 148' w/135 sx. 5 1/2" set @
3642' w/150 sx. Perf. 3088'. Tested 8 5/8" to 500# cement at surface.
Squeezed 5 1/2" w/300 sx. cement blend w/500# hulls mixed in to Max.
P.S.I. 450#. Close in P.S.I. 150#. Plug complete.

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO
Plugged through TUBING , CASING . Elevation: 2131 GL

I did[X] / did not[] observe the plugging.

Carl Goodrow

DATE 5-18-92
INV. NO. 35268

(agent)

Form CP-2/3

STATE CORPORATION COMMISSION
RECEIVED
MAY 11 1992
CONSERVATION DIVISION
WICHITA, KANSAS
5-11-92