

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03378-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 35-10S-19W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: JOHNSON B Well Number: 2  
County: ROOKS Total Vertical Depth: 3625 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 7 feet: 3508  
Surface Casing Size: 12.25 feet: 83

119 81

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2003 12:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 430 sxs 60/40 pozmix - 10% gel - 600# hulls.  
PBTB 3100'. Perfs at 3070' - 3080'. Junk tubing at 2974'.  
Ran tubing to plug.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/10/2003 5:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Welded 13 3/8" to 7" casing. Rigged up.  
Perf Tech perforated 7" casing at 1950' - 1450' - 850'.  
RIH with 2 7/8" tubing to 2512'. Rigged up.  
Allied Cementing pumped 170 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Tubed tubing to 1132'. Pumped 125 sxs cement with 300# hulls to circulate cement to surface.  
TOH with tubing. Tied onto 7" casing. Pumped 40 sxs cement with 600# hulls.  
Max. P.S.I. 400#  
Tied onto 13 3/8" - pumped 30 sxs cement with 100# hulls  
Pressed to 100#. Blew hole in 13 3/8" casing. Casing stayed full..

RECEIVED  
8-13-03  
AUG 13 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET#14746.

Plugged through: TBG

District: 04

100

Signed Dennis L. Hamel  
(TECHNICIAN)

INVOICED  
DATE 8-13-03  
INVOICE # 2003/060396

AYLWARD PRODUCTION CO

#B-2 JOHNSON

35-10-19W  
NW SE NE

Contr.

ROOKS

County

F 2110

Comm 5-10-44

Comp. 8-2-44

IP

20 BOPD  
20 BW

Tops	Depth	Datum
ANH	1425	
LANS	3308	
CONG	3515	
TD	3625	

Casing  
12" 83  
7" 3508

SSO 3385-95: Rip csg  
3078-80:  
Swb 4 BWPB with SSO  
PB 3100: A/1000


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS