

15-163-01999-0000

4-041712

8-15

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 09-19-53

NW NE NW /4 SEC. 01, 10 S, 20 W
330 feet from N section line
3630 feet from E section line

Operator license# 31008

Lease: Wilson 'B' Well # 7

Operator: Paul Bowman Oil Company

County: Rooks 123.21

Address: Box 54
801 Codell Road
Codell, Kansas 67630-0054

Well total depth 3791 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 3/8 Inch @ 221 feet
W/150 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 15 Month: August Year 1995

Plugging proposal received from: Paul Bowman

Company: Bowman Oil Company Phone:

Were: 5 1/2" casing set at 3782' w/125 sxs cement. Perf. At 3779 - 3783'.
Salt at 2200' - Anhy squeeze - Dakota at 975' - W.L.M. 3660' - Casing squeezed at 1690' and 1412' with 200 sxs.
Ordered 225 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls with 10 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 15, Month: August, Year: 1995

Actual plugging report: R.I.H. with tubing to 2300'. Spotted 50 sxs cement with 50# hulls, followed with 5 sxs gel, followed with 50 sxs cement with 50# hulls. Pulled tubing to 1000'. Spotted 50 sxs cement with 200# hulls to circulate at surface. P.O.O.H. with tubing. Squeezed casing with 50 sxs cement. Max. P.S.I. 300#. S.I.P. 100#.

8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 200#. RECEIVED 100#

KANSAS CORPORATION COMMISSION
8-30-95
AUG 30 1995

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING Elevation: GL

I did [X], did not [] observe the plugging.

Dennis L. Hamel (agent)

INVOICED

DATE 8-31-95

INV. NO. 43387

8-15 NOV 02 1995