

6-23-87

To: 6 061272
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 963-22,929 - 0000
SE , SEC. 1, T 10 S, R 20 W/E
1040 feet from S section line
915 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Sutor A Well # 22

Operator: Champlin Petroleum Co.
Name & Union Pacific Res. Co.
Address 1400 Smith St.
Houston, Texas 77002

County Rooks 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size 8 5/8 feet

Surface Casing: Size 8 5/8 feet 261' w/200 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number

Address Wichita, Kansas

Company to plug at: Hour: 7:00 PM Day: 23 Month: June Year: 19 87

Plugging proposal received from Berry Rietz

(company name) Red Tiger Drilling Co. (phone)

were: Order 200 sks 60/40 pozmix 6% Gel 1 sk Flocel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15 PM Day: 23 Month: June Year: 19 87

ACTUAL PLUGGING REPORT

- 1st plug at 3900 w/20 sks.
- 2nd plug at 1665 w/20 sks.
- 3rd plug at 950 w/100 sks and 1 sk Flocel.
- 4th plug at 300 w/40 sks.
- 5th plug at 40 w/10 sks.

Remarks: 10 sks. in rat hole.
(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)
observe this plugging.

DATE 7-10-87

Signed Gilbert G. Scheck D
(TECHNICIAN)

INV. NO. 17464

SEP 17 1987 OCT 30 1987

Gilbert G. Scheck
Dennis Hamel