

4-071105

7-22

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,967-000b

NE SE NE /4 SEC. 01, 10 S, 20 W  
3960 feet from S section line  
330 feet from E section line

Operator license# 5030 Lease Graham well # 6

Operator: Vess Oil Corporation County Rooks

Address: 8100 E. 22nd Street Well total depth 3920 feet  
North Building #300 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67226 Surface pipe 8 5/8 Inch @ 259 feet  
Mike Kasselmann

127.40

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas and Hays, Kansas

Company to plug at: Hour: A.M. Day: 22 Month: July Year: 94

Plugging proposal received from: Mike Kasselmann

Company: Vess Oil Corporation Phone: 316-682-1537

Were: 8 5/8" - 259' S.P. cwc w/200 sxs. cement. 5 1/2" casing set @  
3918' w/200 sxs. cement. F.O. tool set @ 1683' cwc w/400 sxs. Perfs.  
@ 3812' - 2732'. Proposal 350 sxs. 60/40 pozmix - 10% gel and 5 sxs.  
hulls. Pump in with pump truck - bull squeeze 5 1/2" casing top to  
bottom and shut in under pressure. Pressure 5 1/2" x 8 5/8" annulus with  
cement. Shut in under pressure.

Plugging Proposal Received by: Dennis Hamel - Marion J. Schmidt  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 1:30P.M., Day: 22, Month: July, Year: 94

Actual plugging report: Vess Oil ordered 350 sxs. 60/40 pozmix and 5 sxs.  
hulls. Pumped in with pump truck.

- 1) Pumped in (bull squeeze) 5 1/2" casing w/15 sxs. cement - followed  
with 277 sxs. cement w/5 sxs - hulls added - Max. pressure 1000 P.S.I.  
Shut in @ 700# P.S.I.
- 2) Squeezed annulus wouldn't take cement. Max. pressure 500# P.S.I.  
Shut in @ 500# P.S.I.

Remarks: Cemented by Allied Cement.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  , CASING  . Elevation: 2238

I did  did not  observe the plugging.

INVOICED  
DATE 8-15-94  
INV. NO. 40948

[Signature]  
(agent)

RECEIVED  
KANSAS CORPORATION COM  
8-5-94  
AUG 05 1994

RECEIVED  
KANSAS CORPORATION COM  
AUG 05 1994  
Form CP-2/3  
CONSERVATION DIVISION  
WICHITA, KS

7-22 SEP 28 1994